BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZO

Executive En
Byatarayanapu
B.B.M.P., Bang

DRAFT TENDER SCHEDULE

Issued to :

Original / Du
Item No

Name of the Work: Providing Street Signage Board in Ward No. 10 (Doddabor Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rat In Figures
1	80.00	Providing and fixing RCC name board of size 1.35xk0.60x0.04 mtrs fixed in reinforced cement concrete poles of size 0.10x0.10x2.60 mtrs in cement concrete 1:1 $^{1/2:}$:3 proportion using 20 mm and down size graded metal machine mixed with 10 mm dia main steel bars and 8mm dia stripes show in drawing the board shall be provided with 12 mm thick cement plaster in cement mortar 1:3 on both the side, the poles shall be 1:3:6 proportion, the board shall be fixed as per the drawing and at the place indicated by the engineering charge of the work, the cost includes excavation, cost of all materials, cost of steel, centering, transportation, charges, fixing charges etc, the work shall be carried out etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Each	5184.00
2	80.00	Providing and fixing sign board of size 60x60cm equilateral triangle using M.S sheet 5 mm thick with RCC pole of size 0.15x0.15x2.3 mtr made out of cement concrete 1:1$^{1/2}$:3 proportion using 20 mm and down size graded metal machine mixed with 10 mm dia main steel bars and 8 mm dia stirupps as shown in drawing, the poles shall be embedded in the ground for a depth of 0.6 mtrs with cement concrete 1:3:6 proportion, the board shall be fixed as per drawing and at the place indicated by the engineering charge of the work, the cost includes excavation, cost of all materials, cost of steel, centering, transportation charges, fixing charges etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Each	3780.00
3	51.84	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in Hard soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cum	264.60
4	51.84	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cum	73.57

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

Name of the Work: Providing Street Signage Board in Ward No. 10 (Doddabor Vidyaranyapura Sub Division.

5	28.80	Providing and laying in position plain cement concrete of **mix M20 with OPC cement @ 300 kgs, with 20mm** and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cum	5852.52
6	524.80	Painting lines, dashes, arrows etc, on roads in two coats on new work :- painting lines, dashes, arrows etc on roads in two coats on new work with ready mixed road marking paint conforming to IS:164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at the and traffic control etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Sqm	116.64
7	35000	Painting new letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cm	0.70

Signture of the Contractor

Executive Er
Byatarayanapur
BBMP, Banga

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ವಿದ್ಯುಪಡಿಗಳ ಸಂಖ್ಯೆ 11 (2)
ವಿದ್ಯುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-64